ESTIMATE

J.MARCELLA PLUMBING AND HEATING

Date: January 22, 2023
Invoice #: EST
Customer ID: EM

To: Town of Hingham
Eleanor MacKay
Land Use and Development
210 Central Street
Hingham, MA. 02043

Salesperson	Job	Payment Terms	Due Date
Jay	499 Cushing Street	ESTIMATE	1/22/23

Item	Description	Unit Price	Line Total
1.00	Kitchen- Replace kitchen faucet with supplied fixture. Install new		
	flexible stainless steel risers to faucet.		$225.00
2	Main Bath- Sink will not drain.		
	1 1/2" copper DWV line from sink to 2" galvinized drain is clogged.		
	DWV line has been cleared previously by drain company.		
	It is highly probable where copper DWV connects to 2" galvinized		
	piping that a chemical reaction has happened and has closed the		
	the drain port at T. Copper DWV will be removed		
	and installed with 1 1/2" PVC. The drain T will need to be cleared		
	before connection. Kitchen cabinet backing will need to be removed		
	by contractor to gain access to drain line. Without a camera being		
	used to ID trouble, this is first line of correction. If Board wants camera		
	to view before work takes place, Budget Drains is usually the company		
	I refer clients.		
	Stock and Labor		$995.00
		Subtotal	$1,220.00
		Sales Tax	
		Total	**$1,220.00**

Make checks payable to: Jason Marcella