

Memorandum

October 17, 2025

Conservation Department
Attn: Ms. Shannon Palmer
Conservation Officer
Town of Hingham
210 Central Street
Hingham, MA 02043

RE: **Request for Modification to Existing Dock
8 Fulling Mill Lane
DEP #034-1532**

Hingham Conservation Department:

Attached please find a revised Site Plan dated October 17, 2025 for the aforementioned project. In accordance with the October 6, 2025 decision of the Conservation Commission, the existing dock width will be modified to comply with Town of Hingham Regulations for Docks and Piers, Section 23.4(c). The existing structure consists of a 31 ft X 5 ft section and a 20.8 ft X 8 ft section. The width of the planks in the 31 ft X 5 ft section will be reduced to maximum width of 4 ft to comply with Section 23.(c)(1). The existing piles will remain. Approximately eight wooden planks will be installed between the existing piles to provide cross-bracing to support the modified pier on the existing piles. The plank spacing in the modified section shall be a minimum of ¾ inches. The 20.8 ft X 8 ft section serves as a float and will remain as constructed. Silt socks will be installed and maintained throughout construction as shown on the attached plan. The proposed structure shall comply with all other Regulations in Section 23.4(c) as described in the Notice of Intent Project Narrative.

Sincerely,

Merrill Engineers and Land Surveyors



Caroline Rees, P.E.
Project Engineer

Attachment
Enclosure

Cc: M. Coughlin
File 22.732

HANOVER OFFICE:
427 Columbia Road
Hanover, MA 02339
781-826-9200

PLYMOUTH OFFICE:
362 Court Street
Plymouth, MA 02360
508-746-6060

MARINE DIVISION:
26 Union Street
Plymouth, MA 02360
508-746-6060

FALMOUTH OFFICE:
448 N. Falmouth Highway Unit A
North Falmouth, MA 02556
508-563-2183

merrillinc.com



